

**GOVERNMENT OF ANDHRA PRADESH
ABSTRACT**

Rural Development – Mahatma Gandhi National Rural Employment Guarantee Scheme (MGNREGS) – Revision of Rural Standard Schedule of Rates, 2016-2017 (RSSR 2016-2017) – Further Orders – Issued.

PANCHAYAT RAJ AND RURAL DEVELOPMENT (RD.II) DEPARTMENT

G.O.MS.No. 30

Dated: 04-04-2016

Read the following:

- 1) G.O.Ms.No.48, P.R.& R.D. (RD.II) Department, Dated: 28-4-2015.
- 2) G.O.Ms.No.8, P.R.& R.D. (RD.II) Department, Dated: 22-01-2016.
- 3) Government of India, Lr.No.J-11011/1/2009-MGNREGA (Pt), Dt.29.03.2016.
- 4) From the Commissioner, Panchayat Raj & Rural Development, Note No.743/EGS/SPM (T)/2016, Dated:31.03.2016.

<<0>>

ORDER:

The Government vide the G.Os in reference first and second read above have issued orders enhancing the wages for unskilled manual works under MGNREGS from Rs.169/- to Rs.180/- per day with effect from 01.04.2015 duly revising the Rural Standard Scheduled of Rates (RSSR) for the Financial Year 2015-2016 in consonance with the rates fixed for different categories of works taken up under MGNREGS.

2. The Commissioner, Panchayat Raj & Rural Development, AP, Hyderabad, Vide reference fourth read above has stated that, Government of India vide their letter in reference third read above have notified the wage work as Rs.194/- for the year 2016-2017 which will be applicable from 1-04-2016. He has therefore, requested the Government, that in view of enhancement of wage rate for unskilled wage work by Government of India from 180/- to 194/- for the year 2016-2017, Government have also to revise the wage rates issued in references first and second read above.

3. Government after careful examination of the matter, hereby modify certain RSSR rates mentioned in the G.O second read above as detailed in the Annexure to this Order.

4. This order shall comes into effect from 01.04.2016

5. The Commissioner, Panchayat Raj and Rural Development shall take necessary further action in the matter accordingly.

6. The copy of the GO is available on website www.rd.ap.gov.in

(BY ORDER AND IN THE NAME OF THE GOVERNOR OF ANDHRA PRADESH)

**DINESH KUMAR
SPECIAL CHIEF SECRETARY TO GOVERNMENT (RD)**

To

The Commissioner, PR & RD, AP., Hyderabad with a request to communicate to all the concerned officials

All the District Collectors and District Programme Coordinators, NREGS

All the Project Directors, DWMA & Addl. District Programme Coordinators, NREGS

[P.T.O.]

All the Project Directors, DRDAs and Additional District Programme Coordinators, NREGS

All the Chief Executive Officers, ZPs and Additional District Programme Coordinators, NREGS.

The Project Officer, ITDA and Additional District Programme Coordinators of Parvathipuram (Vizianagarm), Srisailam (Kurnool), Paderu (Visakhapatnam), Seethampeta (Srikakulam), Rampachodavaram (East Godavari) & KR Puram (West Godavari)

Copy to:

The Prl. Secretary, Finance (W&P) Dept., Govt. of A.P., Hyderabad.

The Prl. Secretary, PR., Govt. of A.P., Hyderabad.

The Prl. Secretary, Irrigation (I&CAD) of A.P., Hyderabad.

The Prl. Secretary, Tribal Welfare Dept., Govt. of A.P., Hyderabad.

The Secretary, R&B, Govt. of A.P., Hyderabad

The Prl. Secretary, EFS & T Dept., Govt. of A.P., Hyderabad

The Prl. Chief Conservator of Forests, Govt. of AP., Hyderabad

The Commissioner Disaster Management and EO Secy. to Govt.

The Commissioner, AMR-APARD, Rajendranagar, Hyderabad

The Commissioner, Tribal Welfare, Hyderabad

The Chairman and Members of Technical Committee.

The Engineer-in-Chief, Panchayat Raj Dept.

The Engineer-in-Chief, Irrigation Dept.

The Chief Engineer, Tribal Welfare

The Special Officers of NREGS-AP Districts

The Secretary, APREG Council, Hyderabad.

The Superintending Engineers of Panchayat Raj of NREGS -AP Districts.

The Superintending Engineers of Irrigation Dept., of NREGS -AP Districts.

PS to Hon'ble Minister (PR, RWS & NREGS)

PS to Hon'ble Minister (RD, Housing & Sanitation)

PS to Spl. Chief Secretary to Government (RD)

PR&RD (Gent) Dept., (2 copies)

SF/SC

//FORWARDED :: BY ORDER//

SECTION OFFICER

ANNEXURE to G.O.Ms.No.30, PR&RD (RD-II) Department, dated :04/04/2016

Sl. No.	Category No.	Item of Work	Rates approved in RSSR (GO.Ms.No. 48 PR&RD (RD-II)Dept., dated 28.04.2015 & GO.Ms.No. 8 PR&RD (RD-II)Dept., dated22.01.2016)(in Rs.)	Rates now approved to ensure mini. Wage of Rs.194.0/-(in Rs.)	Remarks
1		Unskilled Labour	180.0/ per day	194.0/ per day	-
2	Bush clearance				
	a	Light shrub	4.46/sqm	4.81/sqm	-
	b	Medium and Dense Shrub /Besharam/ Rubber plants	5.64/sqm	6.08/sqm	-
	c	Thin stemmed Juliflora (stem with periphery upto 150 cms)/ thick shrub	11.21/sqm	12.08/sqm	Thick shrub is relevant in tribal areas only
	d	Thick stemmed Juliflora (stem with periphery more than 150 cms)	16.80/sqm	18.10/sqm	-
3	Removal of stumps				
	a	Removal of stumps of girth 30cms to 99cms (small stumps)	130.00 per each	140.10 per each	-
	b	Removal of stumps of girth 100cms to 199cms (medium stumps)	146.23 per each	157.59 per each	-
	c	Removal of stumps of girth 200cms to 299 cms (large stumps)	190.08 per each	204.85 per each	-
	d	Removal of stumps of girth 300cms to 399 cms (large stumps)	248.59 per each	267.91 per each	-
	e	Removal of stumps of girth 400cms to 499 cms (large stumps)	321.72 per each	346.72 per each	-
	f	Removal of stumps of girth 500cms to 599 cms (large stumps)	394.81 per each	425.48 per each	-
4		Removal of water hycinth up to 30cms thick	5.55 /Sqm	5.98 /Sqm	-
5		Removal of water hycinth of more than 30cms thick	7.59 /Sqm	8.17 /Sqm	-

6	Earth work Excavation and depositing on bank with initial lead of 10 mt and initial lift of 2.0 mts in loamy and clayey soils like black cotton soils, red earth and chowdu soils (Ordinary soils)				
	a	Category-I (All works other than trenches, ponds & plantation pitting)	106/ Cum	114.23/ Cum	-
	b	Category II (Trench Cutting works)	180/ Cum	194/ Cum	-
	c	Category III (ponds) up to 1.00 m depth	180/ Cum	194/ Cum	-
	d	Category III (ponds) beyond 1.00 m depth	200/ Cum	215.54/ Cum	-
	e	Category IV (Pitting works)	152.97/ Cum	164.85/ Cum	-
f	Category V (Desilting works)	106/ Cum	114.23/ Cum	-	
7	Earth work Excavation and depositing on bank with initial lead of 10 mt and initial lift of 2.0 mts in Hard soils like gravel, moram., (Hard soils)				
	a	Category-I (All works other than trenches, ponds & plantation pitting)	180/ Cum	194/ Cum	-
	b	Category II (Trench Cutting works)	202.47/ Cum	218.20/ Cum	-
	c	Category III (ponds) up to 1.00 m depth	200/ Cum	215.54/ Cum	-
	d	Category III (ponds) beyond 1.00 m depth	220/ Cum	237.09/ Cum	-
e	Category IV (Pitting works)	180/ Cum	194 / Cum	-	
8	Earth work Excavation and depositing on bank with initial lead of 10 mt and initial lift of 2.0 mts in soils with mixture of gravel, pebble and soft disintegrated rock like shales ordinary gravel, stoney earth and earth mixed with fair sized boulders (Stoney earth)				
	a	Category-I (All works other than trenches, ponds & plantation pitting)	190/ Cum	204.76/ Cum	-
	b	Category II (Trench Cutting works)	198/ Cum	213.38/ Cum	-
	c	Category III (ponds) up to 1.00 m depth	200/ Cum	215.54/ Cum	-
	d	Category III (ponds) beyond 1.00 m depth	220/ Cum	237.09/ Cum	-
e	Category IV (Pitting works)	190/ Cum	204.76/ Cum	-	
9	Earth work Excavation and depositing on bank with initial lead of 10 mt and initial lift of 2.0 mts in soft disintegrated rock soils (removable by pick axes and crow bars) (SDR Soils)				
	a	Category-I (All works other than trenches, ponds & plantation pitting)	202.47/ Cum	218.20/ Cum	-
b	Category II (Trench Cutting works)	240/ Cum	258.64/ Cum	-	

	c	Category III (ponds) up to 1.00 m depth	240/ Cum	258.64/ Cum	-
	d	Category III (ponds) beyond 1.00 m depth	260/ Cum	280.20/ Cum	-
10	Earth work Excavation and depositing on bank with initial lead of 10 mt and initial lift of 2.0 mts in silt in canals, channels and drains				
	a	Feeder/Field Channel and Irrigation drains upto 1.0 mt depth	78.71/ Cum	84.82/ Cum	-
	b	Renovation of spring channels			
11	Earth work Excavation and depositing on bank with initial lead of 10 mt and initial lift of 2.0 mts in sandy soils or loose soils/wet sand not under water				
	a	Land levelling for land development and Flood control Project	59.47/ Cum	64.09/ Cum	-
12	a	Benching with 0.45mx 0.45m size and 0.60mx0.30m size	26.96/ Rmt	29.05/ Rmt	-
13	Carrying of earth / gravel by head loads – Leads & Lifts				
	a	For every additional Lead of 10 mts over and above initial lead of 10mt	22.47/ Cum	24.21/ Cum	-
	b	For every additional lift of 1mt over and above initial lift of 2mts	22.47/ Cum	24.21/ Cum	-
14	Conveyance of silt , carted earth, stable casing soil and gravel excluding loading and unloading				
	a	up to 1 km	58.50/-cum	58.50/-cum	No change
	b	2 km	68.25/-cum	68.25/-cum	
	c	3 km	78/-cum	78/-cum	
	d	4km	87.75/-cum	87.75/-cum	
	e	5km	104/-cum	104/-cum	
	f	6km	107/-cum	107/-cum	
	g	7 km	120/-cum	120/-cum	
	h	8 km	132/-cum	132/-cum	
	i	9 km	138/-cum	138/-cum	
j	10 km	143/-cum	143/-cum		
15		Labour charges for Spreading of silt unloaded by tractor in the field	21.84/ Cum	23.53/ Cum	-
16		Labour charges for breaking clods, trimming, sectioning and manual compaction using Dimmisa	34.01/ Cum	36.65/ Cum	-
17	Pebble bunding				
	a	Small stone (size more than 40mm) bunding- Labour charges for collecting and putting as bund only.	236.22/ Cum	254.57/ Cum	-

18	Stone revetment (Un skilled)					
	a	Labour charges for revetment for all type of works	393.71/ Cum	424.30/ Cum	-	
19	Rough Stone Dry Packing & Stone pitching (Unskilled)					
	a	Rock Fill Dam, Stone Checks & Stone outlets – Labour charges for packing only.	224.97/ Cum	242.45/ Cum	-	
	b	Stone Terracing – Labour charges for packing only.	224.97/ Cum	242.45/ Cum	-	
20	Plantation works					
	Category : I					
	a	Survey and demarcation	29.21/- per100 nos	31.47/- per100 nos	-	
	b	Alignment and fixing of planting point with 0.45 meters length sticks	84.30/- per100 nos	90.85/- per100 nos	-	
	c	0.45 meter sticks preparation and transportation at site.	44.96/- per100 nos	48.45/- per100 nos	-	
	d	i) Internal transportation of bag plants to planting points. (5"x9")	44.96/- per100 nos	48.45/- per100 nos	-	
		ii) Internal transportation of Avenue Plantation. Tall plants	174.57/- per100 nos	188.13/- per100 nos	-	
	e	Refilling of Pits and planting (mxmxm), staking stick				
		i) 0.30 X 0.30 X 0.30 Size pit	1.05/- each	1.13/- each	-	
		ii) 0.45 X 0.45 X 0.45 Size pit	3.30/- each	3.55/- each	-	
		iii) 0.60 X 0.60 X 0.60 Size pit	6.71/- each	7.23/- each	-	
		iv) 0.90 X 0.90 X 0.90 Size pit	10.05/- each	10.83/- each	-	
		v) 1.00 X 1.00 X 1.00 Size pit	11.21/- each	12.08/- each	-	
	Soil working and weeding					
	Category : I (1 M dia and 0.1 m Depth)					
	a	Avenue Plantation	11.21/- each	12.08/- each	-	
	b	Horticulture	11.21/- each	12.08/- each	-	
	Category : II (0.5 M dia and 0.1 m Depth)					
	a	Fore shore plantation	3.30/- each	3.56/- each	-	
	b	B.H.Afforestation	3.30/- each	3.56/- each	-	
c	Bio Diesel Plantation & Block plantation	3.30/- each	3.56/- each	-		
21	Causality Replacement for					
	a	Reopening of Pits for avenue, Horticulture & Blok Plantations.	11.40/- each	12.28/- each	-	

	b	Fore share plantation, Barren Hill Afforestation, Bio-Diesel	5.55/- each	5.98/- each	-
22		Watch & Ward and repair to Fence and soil working of each plant including pruning of branches for plantations raised in common property resource lands and lands of SC/ST/assignees.	180.0/- day	194/- day	-
Bio Fencing / Brush Wood Fencing for barren hill afforestation.					
	a	Nurseries, block plantation and fore shore plantation including collection, transportation and fixing at site	22.46/- Rmt	24.20/- Rmt	-
23	b	Avenue Plantation including collection, transportation and fixing at site (Size of 1 m dia and 1.5 m height)	85.11/- each	91.72/- each	-
	c	Horticulture, for lands of SC-ST & Assignee lands only	2249.89/- acre	2424.70/- acre	-
	d	Horticulture fencing 1 st year & 2 nd year maintenance SC-ST& Assignee lands only.	562.45/- acre	606.15/- acre	-
Deep Ploughing in					
	a	Fallow Land and Hard Gravel soils (Depth not less than 0.3 meters) using ploughing tractors	1487/- acre	1602.54/- acre	-
24	b	fallow land in ordinary soils using ploughing tractor depth not less than 0.3 m	1190/- acre	1282.46/- acre	-
	c	Cattle cultivator (Double ploughing) in ordinary soils.	893.60/- acre	963.03/- acre	-
25		Watering plants of block plantation from the sump constructed (where ever one sump is available per one acre)	2.85/- plant	3.07/- plant	-
26		Watering plants from hand pump/bore well/open well up to distance of 30 mt	4.01/- plant	4.32/- plant	-
27		Watering block plantation from the nearby sources i.e bore well open well or kunta beyond 30 mts distance.	5/- plant	5.38/- plant	-
28		Hire charges of tractor mounted water tanker for filling sump	447/- per one trip of 5000 ltrs capacity	481.73/- per one trip of 5000 ltrs capacity	-
29		Sharpening of crowbar	10/- per day	10.78/- per day	-
30		Basket Replenishment charges	3/- per day	3.23/- per day	-

DINESH KUMAR
SPECIAL CHIEF SECRETARY TO GOVERNMENT (RD)